


## Introducing FlexiArch



Traditional Arch Construction Using Centring

### PAST

Strong

Durable

Aesthetics

### PRESENT

No centring

Fast installation  
(3hrs not 3 months)

Sustainable




FlexiArch



FlexiArch - From flat-pack to arch unit in a matter of seconds

## Skew FlexiArch



Flat geometry of skew FlexiArch

## Research Aims & Objectives

### AIMS:

Develop the following models for the skew FlexiArch system:

- A finite element model to accurately represent the behaviour of the arch under loading
- An analytical model to predict the forces in the polymeric reinforcement for the arch during lifting

The models are verified against the results obtained from an experimental programme, allowing a parametric study on a wider variety of variables to be conducted, eliminating the need for further physical testing.

### OBJECTIVES:


Carry out the following experimental programme:

Experiment Name	Variable			
	Angle of Skew (degrees)	Span to Rise Ratio	Square Span (m)	Rise (m)
ARCH:1/3(5°):15°	15	2.5	1.67	0.67
ARCH:1/3(5°):45°	45	2.5	1.67	0.67
ARCH:1/3(5°):30°	30	2.5	1.67	0.67
ARCH:1/5(10°):30°	30	5.0	2.00	0.40

The results obtained from the experimental programme are compared against a finite element analysis model of the skew FlexiArch system under loading, and an analytical model used to predict the forces in the polymeric membrane during lifting.

## Experimental Progress

- 15° skew FlexiArch has been built and tested; currently building 45° skew arch.
- The arch is constructed using 23 precast concrete voussoirs, held together by polymeric reinforcement and top screed when lifted into its arch form:



Vousoir alignment & polymeric reinforcement prior to casting screed

- Crack inducers allow the screed to crack as the arch shape forms when lifted:




Lifting the skew FlexiArch

- polystyrene wedges used to fill the stepped gaps
- well graded sandy gravel fill (scaled Type 3 GSB) compacted in 200mm layers
- arch loaded at third point under an accurately calibrated hydraulic actuator




Backfilling the skew FlexiArch

## Experimental Results - Lifting



Force in longitudinal polymer element at outer lifting point




Force in transverse polymer element at outer lifting point during lifting

The theoretical FOS for the paragrind was calculated as 10.7, which is comparable to the measured experimental value of 9.7.


## Experimental Results - Load Test




Hinge points on failed skew FlexiArch - mechanism formed - sustained 22.9kN




Change in displacements during full load test




## Finite Element Analysis



Finite element analysis of stepped arch ring loaded at the crown



(a) Reduced width straight edge skew arch ring model  
(b) Skew arch ring model with straight edge  
Straight edged skew arch model



Hinge points on failed skew arch

Failed at 23.2kN; comparable to 22.9kN from the experiment. Hinges in same locations.

## Conclusions

- The skew FlexiArch is a sustainable and viable option for bridges.
- The test results show it to be an efficient structure with the innovative polymer reinforcement working well in carrying the arches self weight during lifting.
- The largest forces in the polymer were during lifting, with the transverse elements taking a negligible force in comparison to the longitudinal elements.
- An analytical model has been developed to predict the forces in the polymeric reinforcement for the arch during lifting.
- A finite element model of the skew FlexiArch was successfully developed, with the results being similar to the experimental test.

## Acknowledgements

The author would like to express his thanks to Dr. Su Taylor, Dr. Des Robinson and Prof. Adrian Long for their continued support and guidance.